



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

### State Corporation Commission

#### CONSERVATION DIVISION (Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

3/2/82  
MAR 2 1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Rudy Herman of Sohio Pet. has this date requested permission to plug the following described well:

Operator's Full Name: Sohio Petroleum Company  
Complete Address: Box 30 Casper Wyoming 82602  
Lease Name: Rostock 'A' Well No. 4  
Location: C52-3E-5W Sec. 3 Twp. 9 Rge. 19 (E) (W)  
County: Rooks Total Depth: 3441  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereafter indicated: \_\_\_\_\_

Mr. Herman was instructed to plug the well as follows:

8 5/8 set @ 314' w/175 sk - 5 1/2" set @ 3437' w/150 - Plug @ 3400 -  
Rocker set above 3194' @ 3100 - Rods parted @ 1500' - 2 1/2" casing parted @ 1288'  
balance of rods & tubing not recovered - hole in 5 1/2" @ 1100' - Ordered 6hulls  
+ 350 sk + 5050 pozmix 6% gel 3 3/8 c.c. + pumped in 2 hulls + 125  
sk in annulus pressure to 500 PSI - shut in - Pumped in 4 hulls and 225 sk  
in 5 1/2" - no pressure - wait 4 hrs - Ordered 6hulls, 150 5050 pozmix  
6% gel 3 3/8 c.c. w/ 1/2# floccle - after 4 hr. wait - pumped in 2 hulls +  
50 cmt - pressure 600 PSI - wait 10-min - pressure held - check annulus  
pressure ok - plugged at 5:00 - 22482 (by Halliburton)

Very truly yours,

Dennis L. Hamel  
Conservation Division Agent