

15-163-30197-00-00

FORM - CP-2
Rev. 9-8-64

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
9/14/66
SEP 14 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Burton of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Building, Wichita, Kansas

Lease Name: Ondrasak Well No. 1

Location: C SE NE NE Sec. 5 Twp. 9 Rge. 19 (E)(W) X

County Rooks Total Depth 3507 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 500' and
displace 25 sc cement thru drill pipe. Heavy mud to 200' set
cementing plug and displace 20 sc cement thru drill pipe. Heavy
mud to 40' set cementing plug 1/3 sc hulls and 8 sc cement to
base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

L. J. Massey
Conservation Division Agent