

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15--005-00312-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date May 28, 1957

Well Operator: Cimarex Energy, Co. (Owner / Company Name) KCC License #: 33094 (Operator's)

Address: RR. 1 Box 83 City: Satanta

State: Kansas Zip Code: 67870 Contact Phone: (620) 276 - 3693 ext. 13

Lease: Johnson Well #: 1 Sec. 9 Twp. 22 S. R. 34 East West

Center - SE/4 - Spot Location / QQQQ County: Finney

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 291 Cemented with: 100 Sacks

Production Casing Size: 5 1/2" Set at: 2613 Cemented with: 300 (not 100% sure of this) Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs: 2530-2534; 2562-2568; 2576-2582; 2609-2611. Plug @ 2586; Cast iron bridge plug set at 2467' on 07/28/06

Elevation: 2954 (G.L. / K.B.) T.D.: 2629 PBTD: 2586 Anhydrite Depth: Stone corral @ 1950' ; Permian top @ 1050'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC instruction. There is a possible casing leak around 500'

(1) CIBP w/2 sx cement @ 1950' (2) CIBP w/2 sx cement @ 1100' (3) Test csg to 750# (4) Perf 4 holes @ 1050' (5) 180 sx 60/40 poz 6% gel down 5 1/2" w/100 hulls after 90 sx (6) if no circulation, 150 sx 60/40 poz 6% gel down 5 1/2" x 8 5/8" per Ken Jehlik 11/06/06

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? The well log was sent in on 09/27/06

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Kent Pendergraft

Phone: (620) 276 - 3693 ext. 13

Address: RR. 1 Box 83 City / State: Satanta, KS 67870

Plugging Contractor: Eagle Well Service KCC License #: 7407

Address: Liberal, KS Phone: (620) 482 - 5637 (Ricky)

Proposed Date and Hour of Plugging (if known?): Soon as application is approved

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 03/20/07 Authorized Operator / Agent: _____

Kent Pendergraft
(Signature)

RECEIVED
MAR 22 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Cimarex Energy Co.
15 East 5th Street - Ste 1000
Tulsa, Ok 74103

March 23, 2007

Re: JOHNSON #1
API 15-055-00312-00-00
SE 9-22S-34W, 1320 FSL 1320 FEL
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



Barry Metz
Deputy Director

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888