

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-22282-00-00

LEASE NAME Deveny

WELL NUMBER No. 2

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1320 Ft. from (S)N Line of Section (circle one)

2310 Ft. from (E)W Line of Section (circle one)

(Formerly drilled by S & K Oil Co.)  
LEASE OPERATOR Liberty Operations & Completions, Inc.

SPOT LOCATION C - W/2 - W/2 - SE

ADDRESS 308 W. Mill

SEC. 25 TWP. 9s S. RGE 18w (W) or (W)

CITY, STATE, ZIP Plainville, Ks. 67663

COUNTY Rooks

PHONE#(913) 434-4686 OPERATORS LICENSE NO. \_\_\_\_\_

Date Well Completed 2/84

Charater of Well T.A. Oil well  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 11/8/96

Date Plugging Completed 11/8/96

The plugging proposal was approved on Emergency plugging authorization by Carl Goodrow 11/8/96 (date)  
by while rig was on hole (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation(s) Lsg. K.C. Depth to Top 3330 Bottom 3554 T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
anhydrite	limestone	1464'	1495'	8 5/8"	208'	none
Topeka	limestone	3072	3288	4 1/2	3617'	none
Lsg. K.C.	shale & limestone	3330	3554			

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 1950 feet to surface feet each set.

Spot 100 sx thru tubing @ 1950' (60/40 poz 10% gel) Pulled tubing squeezed from surface with 80 sx, pressure to 1000# instant shut in 700#. Mix 25 sx squeeze annulus thru braden head to 500# shut in pressure. (used 205 sx 60/40 poz 10% gel 800# cotton seed hulls)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing

License No. NA

Address Russell, Ks.

NAME OF PARTY RESPONDIBLE FOR PLUGGING FEES: Roger Comeau


STATE OF Kansas COUNTY OF Rooks, ss.

Charles D. Farr (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles D. Farr

(Address) \_\_\_\_\_



SUBSCRIBED AND SWORN TO before me this 11 day of November, 1996

Sandra Chard  
Notary Public

My Commission Expires: 9/15/98