

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Continental Resources, Inc.
 Address: P.O. Box 1032, Enid, OK 73702
 Phone: 580-233-8955 Operator License #: 31914
 Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 2/5/07 (Date)
 by: Mike Meier (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
Chester Depth to Top: 5664 Bottom: 5681 T.D. 5830
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-189-20550-00-00
 Lease Name: Cullison
 Well Number: 2-2
 Spot Location (QQQQ): _____ - _____ - NW - SE
1980 Feet from North / South Section Line
1980 Feet from East / West Section Line
 Sec. 2 Twp. 31 S. R. 35 East West
 County: Stevens
 Date Well Completed: 1/29/1982
 Plugging Commenced: 2/7/2007
 Plugging Completed: 2/8/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1734	----
				4 1/2"	5847	1702

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb hulls and 20 sx cement to plug perfs from 5664 to 5464.
4 1/2" was stuck in bottom of 8 5/8". Shot @ 1702', circulate hole w/mud
and mixed 50 sx plug 1700' to 1550', 30 sx plug 550' to 450', 10 sx
plug 40' to 0. Capped 8 5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging Inc. License #: 31151 **RECEIVED**
KANSAS CORPORATION COMMISSION
 Address: Rt #1, Box 49BA, Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Continental Resources, Inc. **APR 10 2007**

State of Oklahoma County, Garfield, ss. **CONSERVATION DIVISION
WICHITA, KS**

Zachary J. Harrel (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Zachary J. Harrel
 (Address) P.O. Box 1032, Enid, OK 73702

SUBSCRIBED and SWORN TO before me this 28 day of March, 20 07

Pamela R. Combest My Commission Expires: 3/8/2009 #01004021
 Notary Public