

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Continental Resources, Inc.

Address: P.O. Box 1032, Enid, OK 73702

Phone: (580-233-8955) Operator License #: 31914

Type of Well: WSW
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)
Docket #: E-27,007 (If SWD or ENHR)

The plugging proposal was approved on: 1/19/07 (Date)

by: Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Wabaunsee - Depth to Top: _____ Bottom: _____ T.D. _____

Council Grove Depth to Top: 2988' Bottom: 3832' T.D. 4324'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-175-20800-00-01

Lease Name: Hampton

Well Number: 17-4

Spot Location (QQQQ): _____ - C - SW - NW

3279 Feet from ☒ North / ☐ South Section Line

4622 Feet from ☒ East / ☒ West Section Line

Sec. 17 Twp. 34 S. R. 34 ☐ East ☒ West

County: Seward

Date Well Completed: 10/4/1990 7/17/92

Plugging Commenced: 1/19/07

Plugging Completed: 1/24/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1717	----
				5 1/2"	4004	2338

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 25 sx cement plug from 2988' to 2788'. WOC tag plug @ 2654.
Shot and pull 5 1/2" to 1750'. Circulate hole w/mud & mixed 50 sx plug
from 1750' to 1600', 30 sx plug from 600' to 500', 10 sx plug from 40'
to 0. Capped 8 5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging Inc License #: 31151

Address: Rt #1, Box 49 BA, Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Continental Resources, Inc.

State of Oklahoma County, Garfield, ss.

Zachary J. Harrel (Employee of Operator) or (Operator) on above-described well

sworn on oath and says: that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Zachary J. Harrel

(Address) P.O. Box 1032, Enid, OK 73702

SUBSCRIBED and SWORN TO before me this 27 day of March, 20 07

Pamela R. Combest My Commission Expires: 3/8/2009 #01004021
Notary Public