

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W. D. Short Oil Co., LLC
Address: P. O. Box 729-102 S. River Rd., Oxford, Ks. 67119
Phone: (620) 455-3576 Operator License #: 33608
Type of Well: ENHR Docket #: E-16,470
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 06-02-2006 (Date)
by: David Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Lime Depth to Top: 3134 Bottom: 3149 T.D. 3149
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 035-19001 - 00 - 01
Lease Name: Wilfred Rahn
Well Number: 1 NE SW NW
Spot Location (QQQQ): C SW SE NW
29703664 Feet from North / South Section Line
36304145 Feet from East / West Section Line
Sec. 11 Twp. 34 S. R. 5 East West
County: Cowley
Date Well Completed: 10-23-1963
Plugging Commenced: 02-13-2007
Plugging Completed: 03-09-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Lime	Water	3134	3149	8-5/8"	221	0
				4-1/2"	3134	1135'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bottom Plug, Sanded Back to 3080' and Dumped 4 sx of Cement on Top of Sand w/ Dump Bailer, Worked Pipe and Shot Off @ 1135',
Laid Down Pipe, Filled Hole w/ Water, Ran 1" to 270' and Pumped 100' Surface, 105 sx w/ 4% Gel, Cleaned and
Restored Location.

Name of Plugging Contractor: Braden Petroleum & Well Plugging CONSERVATION DIVISION WICHITA, KS License #: 32475
Address: P.O. Box 729 Oxford, Ks. 67119
Name of Party Responsible for Plugging Fees: W. D. Short Oil Co., LLC
State of Kansas County, Cowley, ss.
William D. (Don) Short, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 729, 102 S. River Rd. Oxford, Ks. 67119

SUBSCRIBED and SWORN TO before me this 11th day of April, 2007

DENESE A. WILSON
Notary Public - State of Kansas
My Appt. Expires 3-30-09

[Signature] My Commission Expires: 3-30-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

ACT

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
3/27/2007	07/557

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD,KS.67119

JOB LOCATION
WILFRED RAHN #1

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
2/21/2007		MOVED IN ON LOCATION. RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 3080', DUMPED 4 SX. CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG CELLAR, SET JACKS. PULLED SLIPS, WORKED PIPE.	
2/13/2007		WORKED PIPE, SHOT OFF @ 1135'. LAYED OUT 41/2" PIPE. LOADED JACKS, RIGGED DOWN.	
	RIG UP CHARGE		1,200.00T
	PIPE PULLING CHARGE	1135' OF 41/2" PIPE PULLED @ \$0.65 PER FT.	737.75T
	SHOOTING CHARGE	1 SHOT @ \$350.00 PER SHOT	350.00T

RECEIVED
KANSAS CORPORATION COMMISSION
APR 05 2007
CONSERVATION DIVISION
WICHITA, KS

Thank you for your business.	SUBTOTAL	\$2,287.75
	SALES TAX (5.8%)	\$132.69
	BALANCE DUE	\$2,420.44

RECEIVED
KANSAS CORPORATION COMMISSION
APR 13 2007
CONSERVATION DIVISION
WICHITA, KS

B.P.C. WELL PLUGGING

P.O. BOX 282
BURDEN, KS 67019

JAMES R. BRADEN
HOME # 620-438-2856 MOBILE # 620-222-1252

DATE	INVOICE #
3/27/2007	07/562

BILL TO
SHORT COMPANIES
P.O. BOX 729
OXFORD,KS.67119

JOB LOCATION
WILFRED RAHN #1

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
3/9/2007		MOVED IN ON LOCATION. RIGGED UP TO PUMP CEMENT. LOADED 40 BBL. WATER. RUN 1" DOWN INSIDE 85/8" SURFACE PIPE TO 270'. PUMPED 105 SX. CEMENT DOWN 1" FILLED TO THE SURFACE, PULLED 1" OUT. TOPPED OFF WITH CEMENT, WASHED UP. LOADED UP.	
	CEMENT	105 SACKS- 4% GEL @ \$7.35 PER SACK	771.75T
	PUMP CHARGE	3 HRS @ \$75.00 PER HR.	275.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	3 HRS. @ \$50.00 PER HR.	150.00T

Thank you for your business.

SUBTOTAL	\$1,296.75
SALES TAX (5.8%)	\$75.21
BALANCE DUE	\$1,371.96

RECEIVED
KANSAS CORPORATION COMMISSION
APR 13 2007

CONSERVATION DIVISION
WICHITA, KS