

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Continental Resources, Inc.  
 Address: P.O. Box 1032, Enid, OK 73702  
 Phone: 580-233-8955 Operator License #: 31914  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 1/31/07 (Date)  
 by: Jerry Stapleton (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
Chester Depth to Top: 5636' Bottom: 5644' T.D. 5788'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-189-20376-00-02  
 Lease Name: FNO  
 Well Number: 1  
 Spot Location (QQQQ): \_\_\_\_\_ - SW - NE - SE  
1601 Feet from  North /  South Section Line  
905 Feet from  East /  West Section Line  
 Sec. 2 Twp. 31 S. R. 35  East  West  
 County: Stevens  
 Date Well Completed: 4/26/1984  
 Plugging Commenced: 1/31/07  
 Plugging Completed: 2/2/07

KCC  
PICT  
4/13/07  
per  
CPA/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	1652	----
				4 1/2"	5775	1746

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

CIBP plus 2 sx cement 5600' to 5580'. Circulate hole w/mud through 2 3/8". Shot and pull 4 1/2" to 1680'. Circulate hole w/mud and mixed 50 sx cement plug from 1680' to 1530', 30 sx plug from 550' to 450', 10 sx plug from 40' to 0. Capped 8 5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging Inc. License #: 31151  
 Address: Rt #1, Box 49 BA, Tyrone, OK 73951-9731

**RECEIVED  
KANSAS CORPORATION COMMISSION**


Name of Party Responsible for Plugging Fees: Continental Resources, Inc.

**APR 10 2007**

State of Oklahoma County, Garfield, ss.

**CONSERVATION DIVISION  
WICHITA, KS**

Zachary J. Harrel (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that he has knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Zachary J. Harrel

(Address) P.O. Box 1032, Enid, OK 73702

SUBSCRIBED and SWORN TO before me this 27 day of March, 20 07

Pamela R. Combust  
Notary Public

My Commission Expires: 3/8/2009 #01004021

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten initials]*