

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warrior Inc.  
Address: P.O Box 399, Garden City Ks. 67846  
Phone: (620 ) 272 - 1023 Operator License #: 4058  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 4/5/07 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Depth to Top: 3707' Bottom: 3754' T.D. 3825'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 065-03019 - 06-00  
Lease Name: Collison  
Well Number: #3  
Spot Location (QQQQ): C - SE - NW - SW  
1650' Feet from  North /  South Section Line  
4290' Feet from  East /  West Section Line  
Sec. 35 Twp. 9S S. R. 22W  East  West  
County: Graham  
Date Well Completed: 11/25/57  
Plugging Commenced: 4/4/07  
Plugging Completed: 4/4/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	oil	surface	256'	85/8	256'	0
		surface	3821'	51/2	3821'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Log Tech perf 1125' and 1850', 4spf. First plug at 2066', 100sx 60/40 pos 10% gelw/ 300# hulls. 2 nd plug at 1161', 65sx 60/40 poss, 10% gel w/100# hulls, cement circulated. 3rd plug 10sx surface. 10sx down 85/8.

Name of Plugging Contractor: Swift Services inc License #: 32382  
Address: P.O. box 466 Ness City Kansas 67560

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 10 2007  
CONSERVATION DIVISION  
WICHITA, KS

Name of Party Responsible for Plugging Fees: American Warrior Inc.  
State of Kansas County, Finney, ss.  
Jody Smith

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]  
(Address) P.O. Box 399 Garden City Kansas 67846

SUBSCRIBED and SWORN TO before me this 4 day of April, 20 2007  
Erica Kuhlmeier My Commission Expires: 09-12-09  
Notary Public