

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Chaco Energy Co.
Address: P.O. Box 1587
Phone: (303) 744-2034 Operator License #: 31217
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: March 16, 2007 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-055-21926-0000
Lease Name: Estes
Well Number: 1
Spot Location (QQQQ): SW - NW - NW -
740 Feet from ☒ North / ☐ South Section Line
330 Feet from ☐ East / ☒ West Section Line
Sec. 29 Twp. 22 S. R. 30 ☐ East ☒ West
County: Finney
Date Well Completed: 3/17/07
Plugging Commenced: 3/17/07
Plugging Completed: 3/17/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
See ACO-1 (dry hole)		0	340	8.625"	340	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spotted 275 sx 60/40:6 + .25#/sk flocele (1.58 yld/13.8 ppg) cement through drill pipe as follows (bottom (ft)/top (ft)/sx):
2100/1950/50; 1260/1025/80; 660/500/50; 360/140/50; 60/GL/20; rathole/15; mousehole/10

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: H2 Drilling LLC License #: 33793
Address: 6031 10th St, Great Bend, KS 67530
Name of Party Responsible for Plugging Fees: Chaco Energy Co.
State of Colorado County, _____, ss.

Kurt T. Nelson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that he has knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct so help me God.

(Signature) Kurt T. Nelson
(Address) P.O. Box 1587, Denver, CO 80201

SUBSCRIBED and SWORN TO before me this 10 day of April, 2007

Notary Public

My Commission Expires: 11-8-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202