

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22072-00-00

Spot: SW

Sec/Twnshp/Rge: 8-29S-8W

1320 feet from S Section Line,

1320 feet from W Section Line

Lease Name: ZIEGLER

Well #: 2

County: KINGMAN

Total Vertical Depth: 4288 feet

Operator License No.: 4706

Op Name: MESSENGER PETROLEUM, INC.

Address: 525 S. MAIN ST.
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comment
SURE	8.625	230		

\$ 139.36

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/16/2007 4:00 AM

Plug Co. License No.: 5142

Plug Co. Name: STERLING DRILLING COMPANY

Proposal Rcvd. from: GARY TALBOTT

Company: STERLING DRILLING COMPANY

Phone: (620) 672-9508

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

Date/Time Plugging Completed: 01/16/2007 6:45 AM

KCC Agent: GREG EVES

Actual Plugging Report:

Pumped 35 sacks of cement at 1300'. Pulled drill pipe to 700' and pumped 35 sacks of cement. Pulled drill pipe to 280' and pumped 35 sacks of cement. Pulled drill pipe to 60' and pumped 25 sacks of cement and circulated to surface. Pumped 15 sacks of cement in rathole and pumped 10 sacks of cement in mousehole.

155 sacks total of 60/40 posmix with 4% gel ticket #15448

Perfs:

RECEIVED
KCC DISTRICT #2

JAN 15 2007

WICHITA, KS

INVOICED
DATE 4-17-07
INV. NO. 2007061617

Remarks:

Plugged through: DP

District: 02

Signed

Greg Eves

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS