

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00335-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 1-30S-7W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: REIDA Well #: 1
County: KINGMAN Total Vertical Depth: 4201 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 SOUTH MAIN - SUITE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4199		95 SX
SURF	8.625	250		90 SX

\$ 136.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/15/2006 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUG BACK WITH SAND TO 4075 FT. USE DUMP BAILER TO DUMP 5 SX CEMENT ON TOP OF SAND. CUT AND RECOVER 5 1/2" CASING. SPOT CEMENT AS REQUIRED BY THE KCC REPRESENTATIVE WHILE COMING OUT OF HOLE AND PLUG TOP HOLE AS REQUESTED.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/21/2007 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS. WERE COVERED WITH SAND FROM 4169 TO 4075' AND CAPPED WITH 5 SKS OF CMT.. CASING WAS RECOVERED FROM 2470' AND PULLED TO 1200' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35SKS OF CMT. WAS SPOTTED. CASING WAS PULLED TO 300' AND CMT. WAS CIR. TO SURFACE. CASING WAS PULLED AND WELL TOP OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
4125	4135		SEE NOTE


INVOICED
DATE 4-17-07
INV. NO. 2007 061618

Remarks: ALLIED CEMENTING CO. TICKET# 24337 60/40 POZMIX 4 % GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

