

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21420-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 16-33S-6W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WILSON TRUST Well #: 2
County: HARPER Total Vertical Depth: 4500 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4499		
SURF	8.625	252		175 SX \$ 146.25

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/12/2007 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD NCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PER KCC RECOMMENDATIONS.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 03/12/2007 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE COVERED WITH SAND FROM 4449-4370' AND CAPPED WITH 4 SKS OF CMT.. THE CASING WAS RECOVERED FROM 3420' AND PULLED TO 1200' WHERE 35 SKS WERE SPOTTED. CASING WAS PULLED TO 700' WHERE 35 SKS OF CMT. WAS SPOTTED. CASING WAS PULLED TO 300' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING PIPE WAS PULLED AND CMT. TOPPED OFF WELL.

Perfs:


Top	Bot	Thru	Comments
4420	4424		MISSISSIPPI CHER

INVOICED
DATE 4-17-07
INV. NO. 2007061619

Remarks: ALLIED CEMENTIN CO. TICKET # 32455 60/40 W/ 4% GEL

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

