

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00202-00-01
Spot: NESWSE Sec/Twnshp/Rge: 9-32S-7W
1021 feet from S Section Line, 1652 feet from E Section Line
Lease Name: MUIR Well #: 1
County: HARPER Total Vertical Depth: 4835 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4780		200 SX CMT
SURF	8.625	215		180 SX CMT \$ 157.14

Well Type: SWD UIC Docket No: D08443.0 Date/Time to Plug: 02/22/2007 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: Phone: (620) 727-3410

Proposed Plugging Method: AS KCC REQUIRES. SAND BACK 50' ABOVE PACKER, PLACE 5 SKS CMT. @1250', 35SKS, 35 SKS @ 700', CIRC CMT FROM 270' TO SURFACE. - PKR STUCK IN HOLE. SHOT TUBING OFF ABOVE PACKERT. SANDED BACK FROM PACKER @3650' TO 3580' AND CAPPED WITH 5 SKS CMT. REC 3010' PIPE, 35 SKS @ 1250', 35 SKS 700', CIRC. CMT FROM 270' TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/22/2007 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE WELL WAS SANDED BACK FROM TOP OF PACKER AT 3650' TO 3580' AND CAPPED OFF WITH 5 SKS CMT.. THE CASING WAS RECOVERED FROM 3010' AND PULLED TO 1250' WHERE 35 SKS OF CMT. WAS SPOTTED IN PLACE. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED IN PLACE. THE CAING WAS PULLED TO 270' WHERE CMT. WAS SPOTTED AND CIRC. TO SURFACE WITH 75 SKS CMT..

Perfs:


INVOICED
DATE 4-17-07
INV. NO. 2007061620

Remarks: ALLIED CEMENTING CO. 60/40 POSMIX 4% GEL, TICKET # 32459

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

