

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22520-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 22-21S-10W  
400 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: CAYWOOD Well #: 1-22  
County: RICE Total Vertical Depth: 3540 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1670 BROADWAY #3300  
DENVER, CO 80202

Summary 8.625 332 per RBDMS  
Pkt 4/16/07

\$ 115.05

Well Type: OH DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/14/2007 3:30 PM

Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY

Proposal Rcvd. from: CARL JESSEPH Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Pumping Method: Pump 35sx@3447', 35sx@1250', 35sx@800', 35sx@380', 25sx@60' to surface, 15sx in Rathole, 10sx in Mousehole.

Plugging Proposal Received By: GREG EVES

WitnessType: NONE

Date/Time Plugging Completed: 03/14/2007 6:30 PM

KCC Agent: GREG EVES

Actual Plugging Report:

Perfs:

Pumped 35 sx @ 3447' (Arbuckle), Pulled drill pipe to 1250' and pumped 35 sx, Pulled drill pipe to 800' and pumped 35sx, Pulled drill pipe to 380' and pumped 35sx, Pulled drill pipe to 60' and pumped 25 sx to circulate to surface. Pumped 15 sx in Rathole, Pumped 10 sx in Mousehole.

**INVOICED**  
DATE 4-17-07  
INV. NO. 2007061621

Remarks: JET STAR TICKET # 14414 TOTAL = 190 SX 60/40 POZ 4% GEL

Plugged through: DP

District: 02

Signed

Greg Eves

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 10 2007

CONSERVATION DIVISION  
WICHITA, KS