

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19044-00-00

Spot: NWNWNE

Sec/Twnshp/Rge: 15-17S-4E

4987 feet from S Section Line, 2295 feet from E Section Line

Lease Name: ED RIFFEL

Well #: 2

County: MARION

Total Vertical Depth: 2354 feet

Operator License No.: 5192

Op Name: SHAWMAR OIL & GAS CO., INC.

Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String Size Depth (ft) Pulled (ft) Comment

PROD 5.5 2337

SURF 8.625 104

76.51

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/15/2007 9:30 AM

Plug Co. License No.: 33307

Plug Co. Name: FLINT HILLS OIL CO., LLC

Proposal Rcvd. from: BEAU J. CLOUTIER, PRESI Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 382-2932

Proposed
Plugging
Method:

Sand to 2,285' & top with 5 sxs. cement. Shoot casing off & pull same. Run tubing to 250' & circulate cement to surface.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 03/15/2007 11:30 AM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 2,285' & topped with 5 sxs. cement. Shot casing off @ 1,750' & pulled same. Ran tubing to 300' & circulated 194 sxs. cement to surface.

INVOICED
DATE 4-17-07
INV. NO. 2007061623

Remarks: USED 60/40 POSMIX W/4% GEL BY CONSOLIDATED. INVOICE #17081.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS