

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01392-00-00
Spot: SWSESE Sec/Twnshp/Rge: 22-20S-3W
344 feet from S Section Line, 1088 feet from E Section Line
Lease Name: SCHRAG Well #: 5
County: MCPHERSON Total Vertical Depth: 3081 feet

Operator License No.: 32778
Op Name: CAT ENERGY, LLC
Address: PO BOX 507
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3079	570	
SURF	8.625	202		

\$ 100.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/27/2006 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DUANE PURSER Company: CAT ENERGY, LLC Phone: (316) 734-8911

Proposed Plugging Method: Sand to 3020' and top with 4 sacks of cement. Shoot casing off. Pull casing to 525' and spot 35 sacks of cement. Pull casing to 260' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/27/2006 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

11/27/2006 -- Ran wireline to 1250' and hit bridge. Pumped 20 bbls water down 4-1/2" casing. Ran wireline to 1800' and hit bridge. Pumped 20 bbls of water down 4-1/2" casing. Ran wireline to 2350'.

11/28/2006 -- Pumped 40 bbls of water down 4-1/2" casing and 19 bbls of water flowed back. Copeland ran wireline to 2318' and hit solid bridge. Perforated casing at 2310'. Ran 2-3/8" tubing to 2285'.

11/29/2006 -- Circulated outside and inside of casing. Pumped 35 sacks of cement (15 sacks inside and 20 sacks outside) of 4-1/2" casing. Ripped casing at 570'. Pulled casing to 542'.

11/30/2006 -- Rigged up and spotted 35 sacks of cement at 542'. Pulled casing to 289' and circulated 200 sacks of cement to surface.

12/1/2006 -- Checked top plug; cement 5' below ground level.

60/40 posmix with 4% gel
Copeland #31271 & #31272

Perfs:

RECEIVED
KCC DISTRICT #2
JAN 23 2007
WICHITA, KS

INVOICED
DATE 4-16-07
INV. NO. 2007061606

Remarks:

Plugged through: TBG

District: 02

Signed Michael R. Wilson
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

MH

PLG