

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20152-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 20-18S-10W  
3630 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ROSE BIEBERLE Well #: 2  
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 403 FRONT STREET  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3300		200 SX CMT
SURF	10.75	240		175 SX CMT

# 107.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/11/2007 1:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: See actual plugging report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: NONE  
Date/Time Plugging Completed: 01/11/2007 5:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Ran tubing to 3200' and pumped 35 sacks of cement. Perforated at 1250', 900', and 290'. Ran tubing to 1250' and pumped 35 sacks of cement. Pulled tubing to 900' and pumped 35 sacks of cement. Pulled tubing to 290' and circulated cement; let stand 1-1/2 hours. Circulated more cement with 150 lbs pressure after 1-1/2 hours; on backside of 5-1/2", also.

60/40 posmix with 4% gel

Copeland #C-031406  
Log Tech #4810

Perfs:

Top	Bot	Thru	Comments
3279	3280		
3270	3271		
3262	3263		

RECEIVED  
KCC DISTRICT #2  
JAN 24 2007  
WICHITA, KS

INVOICED  
DATE 4-16-07

INV. NO. 2007061607

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

APR 10 2007

CONSERVATION DIVISION  
WICHITA, KS

*m*

*PKF*