

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21244-00-00
Spot: E2E2 Sec/Twnshp/Rge: 10-31S-7W
2640 feet from S Section Line, 660 feet from E Section Line
Lease Name: MATHES Well #: 1B
County: HARPER Total Vertical Depth: 4448 feet

Operator License No.: 33513 •
Op Name: FIVE STAR ENERGY, INC.
Address: 215 E. 14TH ST.
HARPER, KS 67058

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4320		100 SX
SURF	8.625	245		175 SX

\$144.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2007 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PER KCC REGULATIONS.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/15/2007 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE COVERED WITH SAND FROM 4448 TO 4270' AND CAPPED WITH 5 SKS CMT.. THE CASING WAS RECOVERED FROM 3250' AND PULLED TO 1300', WHERE 35 SKS OF CMT. WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35SKS OF CMT. WAS SPOTTED. THE CASING WAS PULLED TO 300' WERE CMT. WAS CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4320	4325		

INVOICED


DATE 4-16-07
INV. NO. 200 7061609

Remarks: UNTIED CEMENT CO. TICKET # 7681 60/40 POZMIX 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

m

P157