

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01635-00-02
Spot: NWNWNE Sec/Twnshp/Rge: 30-27S-10W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: MILES A Well #: 5
County: KINGMAN Total Vertical Depth: 4220 feet

Operator License No.: 6969
Op Name: THE GEMINI OIL COMPANY
Address: 427 SOUTH BOSTON STE 320
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3390		385
SURF	12.5	317		225

\$ 137.15

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/26/2007 8:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: STEVE A. GEDDIE Company: GEMINI OIL CO. Phone: (918) 582-3935

Proposed Plugging Method: SAND BACK TO 2450' & CAP W 10 SX CMT -NO CASING PULLED- PERF @1400' SPOT 50SX -PERF @950' SPOT 50SX - PERF 370' & CIRC BACKSIDE TO SURFACE, FILL 7' TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 02/28/2007 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SAND BACK TO 2281' TAGGED TOPPED WITH 6 SX OF CEMENT. PERF AT 1400 RAN 50 SX CEMENT SET FOR 2 HRS. COULD NOT TAG, RAN ANOTHER 50SXS CEMENT SET OVERNIGHT, TAGGED NEXT DAT @ 1140'. PERF 2 950' WITH 50 SX CEMENT TAGGED AT 875. PERF AT 385' AND CIRC. CEMENT TO SURFACE WITH 300 SX CEMENT. REMOVED TOP VALVE, CEMENT AT VALVE- FILLED 7" WITH 6 SXS. ON 03/09/07.

Perfs:

Top	Bot	Thru	Comments
2502	2530		


INVOICED

DATE 4-16-07
INV. NO. 2007061610

Remarks: JET STAR CEMENTING COMPANY- TICKET# 16003 PBDT 2600'

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3
APR 10 2007
CONSERVATION DIVISION
WICHITA, KS



