

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00397-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 25-30S-8W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: STEVENS Well #: 1
County: KINGMAN Total Vertical Depth: 4410 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 13727 NOEL RD., STE 500
DALLAS, TX 75240

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-------------|
| PROD | 5.5 | 4410 | | 150 SX CMT. |
| SURF | 8.625 | 289 | | 175 SX CMT. |

\$ 143.33

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2007 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SEE ATTACHED P & A PROCEDURES. PERFS 4272-4280, 4300-4308, PBTD 4370', SAND TO 4225' AND 5 SJS CMT., REC CASING, 35SKS 1250', 35 SKS 700', CIRC CMT. 340'-0'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 02/12/2007 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED FROM 4370'-4225' AND CAPPED WITH 5 SKS CMT. NO CASING RECOVERY, NO STRETCH. PERF'D 1250' SQUEEZES 35 SKS CMT.; PERF'D 700', SQUEEZES 35 SKS CMT.; PERF'D 340' ,AND CIRC. CMT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4300 | 4308 | | |
| 4274 | 4280 | | |

INVOICED

DATE 4-17-07
INV. NO. 2007061616

Remarks: ALLIED CEMENTING CO. COMMON 3 CACL TICKET # 24492

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

0

PET