

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00892-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 23-30S-8W  
2300 feet from N Section Line, 1000 feet from E Section Line  
Lease Name: WEST SPIVEY UNIT Well #: 11  
County: KINGMAN Total Vertical Depth: 4401 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4399	3260	
SURF	8.625	200		

\$ 143.03

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2007 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: SARAH BENNETT Company: \_\_\_\_\_ Phone: (972) 628-1478

Proposed Plugging Method: SEE ATTACHED P & A PROCEDURES. SAND BACK 50' ABOVE PERFS, CAP WITH 5 SKS, @1250', 35 SKS @750', CIRC CMT. 250 TO SURFACE

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/29/2007 12:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4230', SAND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3260' AND PULLED TO 1250', WHERE 35 SKS OF CMT. WAS SPOTTED. THE CASING WAS PULLED TO 750', WHERE 35 SKS OF CMT. WAS SPOTTED. THE CASING WAS PULLED TO 250' WHERE CMT. WAS CIRC. TO SURFACE. - CASING PULLED AND CMT TOPPED OFF WELL.

Perfs:

Top	Bot	Thru	Comments
4282	4312		MISSISSIPPI

**INVOICED**  
DATE 4-17-07  
INV. NO. 2007061614

Remarks: ALLIED CEMENTING CO. 60/40 POSMIX 4% GEL TICKET #

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
FORM CP-2/3

APR 10 2007

CONSERVATION DIVISION  
WICHITA, KS