

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19609-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 8-25S-5E  
1750 feet from N Section Line, 330 feet from W Section Line  
Lease Name: WILSON A Well #: 209  
County: BUTLER Total Vertical Depth: 2036 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PARKWAY, BLDG  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2149		UNKNOWN
SURF	6.625	1972		

\$ 66.17

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2006 8:00 AM  
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.  
Proposal Rcvd. from: CASEY COATS Company: \_\_\_\_\_ Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/14/2006 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

11/14/06 MIRU SIMMONS WELLS SERVICES, RIH W/TBG @ 920', LOAD HOLE, CIR. OIL FROM CSG. & UNITED CEMENTING CO. MIXED AND PUMPED 35 SXS CLASS "A" 3% CC, POOH W/TBG WAITED HR. RIH TAGGED CEMENT @ 696'. PRESSUED CASING @ 200#, HELD OK RIH PERFORATED CASING @ 250-251'. SWEDGED INTO 6-5/8" . ESTABLISHED CIRCULATION, UNTIED CEENTING MIXED & PUMPED 189 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETED 1340 PM 11/14/2006

INVOICED  
DATE 4-17-07  
INV. NO. 2007061625

Remarks: CIBP @ 975' PERFS 831-860', 928-944', UNITED CEMENTING CO. TICKET # 7416

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

APR 10 2007

CONSERVATION DIVISION  
WICHITA, KS

*(Handwritten mark)*

*(Handwritten mark)*