

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-00325-00-01
Spot: NENESE Sec/Twnshp/Rge: 26-26S-9W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: BRUCH Well #: 1-26
County: RENO Total Vertical Depth: 4438 feet

Operator License No.: 33650
Op Name: WEST BAY EXPLORATION CO.
Address: 13685 S. WEST BAY SHORE #200
TRAVERSE CITY, MI 49684

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	8.625	210		
SURF	5.5	4408		

\$ 144.24

Well Type: OK DH ^{KCC PROD} _{4/16/07} _{CPH} UIC Docket No: _____ Date/Time to Plug: 12/11/2006 9:00 AM
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC
Proposal Rcvd. from: CHUCK SCHMIDT Company: WEST BAY EXPLORATION CO. Phone: (316) 755-3523

Proposed Plugging Method: CIBP at 4240' and top with 2 sacks of cement. Pull casing to 1250' and spot 35 sacks of cement. Pull casing to 850' and spot 35 sacks of cement. Pull casing to 260' and circulate cement to the surface.

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: PARTIAL
Date/Time Plugging Completed: 12/13/2006 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:
12/11/2006 -- Set CIBP at 4240' and topped with 2 sacks of cement. Shot 5-1/2" casing off at 3256'. Pulled casing to 1630' and hole unloaded. Rigged up cementers and pumped 225 sacks of cement and shut well in.
12/12/2006 -- Ran wireline inside of 5-1/2" casing and tagged cement at 1585'. Shot casing. Tried to pull casing at 1304', but it wouldn't come free. Shot casing loose at 880'.
12/13/2006 -- Pulled casing to 757' and spotted 35 sacks of cement. Pulled casing to 260' and circulated 175 sacks of cement to the surface.
60/40 posmix with 4% gel
Jet Star Energy #14263 & #15398

Perfs:
**RECEIVED
KCC DISTRICT #2
JAN 23 2007
WICHITA, KS**

INVOICED
DATE 4-17-07
INV. NO. 2007061626

Remarks:
Plugged through: CSG

District: 02 Signed Michael R. Wilson

(TECHNICIAN)
RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2007
Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS

M

[Signature]