

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21022-00-00
Spot: SENWSE Sec/Twnshp/Rge: 33-15S-26W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BABCOCK Well #: 1
County: GOVE Total Vertical Depth: 4575 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N. PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4223	0	550 SX
SURF	8.625	215	0	150 SX

\$ 148.69

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2007 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2007 12:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 215' w/150 sxs cement.
4 1/2" production casing set at 4223' w/550 sxs cement.
No information available in regards to DV tool, port collar or perforation.
PBT 4107'. TD 4575'
Connected to 4 1/2" production casing - pumped 220 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Connected to 8 5/8" surface casing - pumped 5 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4087	4092		
4075	4079		
4049	4054		

INVOICED
DATE 4-18-07
INV. NO. 2007061628

RECEIVED
KANSAS CORPORATION COMMISSION
APR 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #30741.

Plugged through: CSG

District: 04

100.

Signed Darrel Dipman
(TECHNICIAN)

APR 06 2007

PKT


SOURCE PETROLEUM
910 CENTURY PLAZA BLDG. #1 BARCOCK
WICHITA, KS. 67202

33-15-26W
SE NW SE

CONTR BLUE GOOSE DRILLING CTY GOVE

GEOL STEVE MURPHY FIELD JUDICA EXT (1/4 N)

ELV 2597 KB SPO 5/23/86 CARD ISSUED 7/24/86 IP P 35 80 & 100 BWPD
DRLG COMP 5/31/86 LKC 4049-4089 OA
(NEW PAY)



LOG	Tops	Depth/Catum	
ANH	2019+	578	API 15-063-21,022
HEEB	3845	1248	8 5/8 " 215 / 150 SX, 4 1/2 " 4223 / 550 SX
LANS	3886	1289	NO CORES
STARK	4127	1530	DST (1) 4042-4055 (LKC) / 45-45-45-60, 180' GIP, REC 120'
BKC	4183	1586	CLEAN GSY OIL, 60' GSY HOCM (40% OIL), SIP 1056-1012#, FP 21-43 / 64-75#, HP 1952-1941#
FT SC	4388	1791	DST (2) 4068-4100 (LKC) / 30-45-45-60, 755' GIP, REC 185'
CHER	4414	1817	CLEAN GSY OIL, 30' GSY HOCM (30% OIL), 30' GSY MC OIL (20% OIL), SIP 1293-1271#, FP 43-53 / 75-96#, HP 2094-1985#
MISS DOL	4485	1888	DST (3) 4102-4171 (LKC) / 30-30-30-30, REC 120' OIL SPKD M, SIP 1153-1099#, FP 53-64 / 96-96#, HP 2104-2083#
PBTD	4105	1508	DST (4) 4380-4415 (FT SC) / 30-30-10-30, REC 5' M, SIP 96-96#, FP 21-21 / 53-53#, HP 2268-2225#
LTD	4574	1977	DST (5) 4490-4500 (MISS DOL) / 20-30-10-45, REC 5' M, SIP
RTD	4575	1978	

1244-1244#, FP 22-33 / 55-55#, HP 2408-2308#

MICT - CO, PF (LKC J) 4115-4119, AC 250 GAL (15% DSFE), SWB 3 BFPH (5% OIL), NON-COMMERCIAL, SET CIBP AT 4110, PF (LKC I) 4076-4089, AC 500 GAL (15% DSFE), SWB 6 BFPH (80% OIL), PF (LKC H) 4049-4054, AC 250 GAL (15% DSFE), SWB 6 BFPH (50% OIL), SION, ONFU 3000' TF (500' OIL ON TOP), SWB 10.5 BFPH (55% OIL), POP, P 35 80 & 100 BWPD, 6/14/86