

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20841-00-00
Spot: NWNESE Sec/Twnshp/Rge: 2-20S-12W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: DEWERFF Well #: 2
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3339	0	250 SX
SURF	8.625	255	0	225 SX

\$ 108.88

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2007 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2007 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing & Salvage, Inc. pulled rods from well.
Pulled 26 joints tubing - got stuck in the hole.
Turned tubing off and recovered 10 more joints.
Kelso RIH with 1" to 320'. Copeland rigged to 1" and pumped 75 sxs 60/40 pozmix with 750# PIP to circulate cement up 4 1/2" casing and 8 5/8" casing.
Kelso pulled 1" tubing. Copeland rigged to 4 1/2" casing and pumped 10 sxs 60/40 pozmix to circulate cement out of 8 5/8".
Shut backside and pumped 100 sxs 60/40 pozmix down 4 1/2", followed with 90 sxs cement with 100# hulls mixed in.
Max. P.S.I. 400#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3339	3350	OH	Arbuckle

INVOICED
DATE 4-18-07
INV. NO. 2007061630

RECEIVED
KANSAS CORPORATION COMMISSION
APR 13 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #019334.

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

APR 10 2007

PK

CORRECTED CARD

FELL & WOLFF OIL CO.
 P.O. BOX 7447, TULSA, OKLA.
 CONTR H-30, INC.

#2 DEWERFF

2-20-12W
 NW NE SE

CTY BARTON

GEOL VIC REISERER

FIELD HAMMER

1797 KB 2/25/75 CARD
 CM 7/31/75 ISSUED

IP P 30 BOPD NW

ARB OH 3339-50

API 15-009-20,841

+	+	+
+	+	+
+	+	+

SMP TOPS	DEPTH	DATUM
HEEB	2957	-1160
BR LM	3077	-1280
LANS	3095	-1298
ARB	3336	-1539
TD	3350	-1553

8 5/8" 255, 4 1/2" 3339

NO LOG

DST (1) 3339-50/45-45-45-45, REC 100'

GIP, 790' CL GSY O, 270' M GSY O,

90' HO&GCM, SIP 1216-1174#, FP 84-

589#

MICT - CO, ON/FU 1900', SWB 2 BOPH, NAT,
 AC 250, SWB 13 BOPH, AFTER LD, POP

CORRECTED CARD: 8/7/75

CORRECTED POTENTIAL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS