

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19001-00-01
Spot: NESWNW Sec/Twnshp/Rge: 11-34S-5E
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WILFRED RAHN Well #: 1
County: COWLEY Total Vertical Depth: 3149 feet

Operator License No.: 6679 33608 Per T-1
Op Name: W.D. Short Oil Co. LLC
SHORT, W.D. AND MARJORIE DBA W.
Address: PO BOX 1 102 S. River Rd PO Box 729 SURF 8.625 221 175 SX CMT \$10234
OXFORD, KS 67119

Well Type: EOR UIC Docket No: E16740.2 Date/Time to Plug: 02/21/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: B.P.C. WELL PLUGGING Phone: (620) 222-1252

Proposed Plugging Method: PER KCC INSTRUCTION.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/09/2007 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

02/21/2007- SANDED BACK 54' ABOVE PERFS. @3080', DUMP BAILED 4 SXS
CEMENT ON TOP. 2/28/07 SHOT 4.5 CSG @ 1280', LAYED DOWN CASING. 3/9/07 RIH
W/TBG @ 270', B.P.C. WELL PLUGGING MIXED & PUMPED 105 SXS. 60/40 POZMIX
4% GEL TO SURFACE. P.A. COMPLETE 11:00AM 03/09/07

Perfs:

Top	Bot	Thru	Comments
3134	3149		

INVOICED
DATE 4-24-07
INV. NO. 2007061646

Remarks: DOCKET #E-16,740, PERFS OH 3134'-3149'- TICKET #07-562

Plugged through: TBG

District: 02

Signed

Duane R. Krueger

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

APR 10 2007

CONSERVATION DIVISION
WICHITA, KS

ART