

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21169-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 35-9S-22W  
1650 feet from S Section Line, 330 feet from W Section Line  
Lease Name: COLLISON Well #: 6  
County: GRAHAM Total Vertical Depth: 3842 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250	0	w/190 sxs cmt
SURF	5.5	3835	0	w/200 sxs cmt

\$ 124.87

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2007 2:00 PM  
Plug Co. License No.: 33669 Plug Co. Name: WESTERN WELL DRILLING, LLC  
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/11/2007 5:10 PM KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing in to 2060' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1030' - pumped 200 sxs cement with 200# hulls - no circulation.  
Let set one hour.  
Pulled tubing to 510' - pumped 65 sxs cement - good cement circulation.  
Pulled tubing and topped off with 10 sxs.  
Dug out backside - found full of cement.

**Perfs:**

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed 

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION CP-2/3

APR 16 2007

CONSERVATION DIVISION  
WICHITA, KS

APR 12 2007

*PT*

THE MAURICE L BROWN COMPANY  
 200 SUTTON PLACE  
 WICHITA, KS 67202

#6 CALLISON

35-9-22W  
 SW NW SW

CONTR ABERCROMBIE DRILLING CTY GRAHAM

GEOL HARLAN DIXON FIELD BRASSFIELD

E 2358 KB CM 9/15/79 CARD ISSUED 1/24/80 IP P 10 BO & 100 BWPD  
 LKC 3779-3802 OA

+	+	+
+	+	+

API 15-065-21,169

LOG	TOPS	DEPTH	DATUM
SC		1847	+ 511
HEEB		3558	-1200
LANS A		3596	-1238
LANS B		3609	-1251
LANS C		3636	-1278
LANS D		3652	-1294
LANS E		3671	-1313
LANS F		3681	-1323
LANS G		3693	-1335
LANS H		3735	-1377
LANS I		3761	-1403
LANS J		3777	-1419
LANS K		3798	-1440
LANS L		3814	-1456
BKC		3826	-1468
RTD		3840	-1482

B-5/8" 250/190sx, 5 1/2" 3835 1/2/200sx  
 DST (1) 3617-35 (LANS C)/60-60-60-60,  
 496' MSW, SIP 524-524#, FP 16-180/  
 180-246#, HP 1803-1771#  
 DST (2) 3635-55 (LANS D)/60-60-90-60,  
 30' DM, SIP 638-622#, FP 25-33/33-  
 41#, HP 1803-1787#, BHT 122°  
 DST (3) 3668-85 (LANS F)/60-60-60-60,  
 735' MSW, NSO, SIP 492-492#, FP  
 33-221/230-312#, HP 1835-1811#,  
 BHT 128°  
 DST (4) 3715-35 (LANS H)/60-60-90-60,  
 10' SOCM, 238' MSW, SIP 557-541#,  
 FP 16-74/74-131#, HP 1827-1811#,  
 BHT 128°

(OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS