

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JUN - 8 1966
 6-8-66
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Cain of Peel Bros. Drilling Co. has this date requested permission to plug the following described well:

Mr. Cain guarantees payment of the plugging fee.

Operator's full Name: Nadel-Gussman

Complete Address: 625 Union Center, Wichita, Kansas

Lease Name: Graham Well No. 4

Location: C S/2 N/2 NW Sec. 29 Twp. 9 Rge. 20 (E)(W) X

County Rooks Total Depth 3885 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cain was instructed to plug the well as follows:

Gun pits, Circulate heavy mud, Set cementing plug at 550 Ft.
and displace 20 sax cement thru drill pipe. Heavy mud to 200 Ft.
set cementing plug and displace 20 sax cement thru drill pipe.
heavy mud to 40 Ft. Set cementing plug, 1/3 sax hulls, and 10
sax cement to base of cellar. Plug rat hole with 2 sax cement.

Very truly yours,

Leo Massey
 Conservation Division Agent