


WELL PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

OR FORMATION PLUGGING RECORD Strike out upper line when reporting plugging off formations.

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Rooks County. Sec. 18 Twp. 9S Rge. 20 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SE SE NW Lease Owner The Palmer Oil Corporation, etal Lease Name Miller "A" Well No. 1 Office Address 415 Union National Bank Building, Wichita 2, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed 6/30/51 19 Application for plugging filed 6/30/51 19 Application for plugging approved 6/30/51 19 Plugging commenced 6/30/51 19 Plugging completed 6/30/51 19 Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Producing formation Depth to top Bottom Total Depth of Well 3839 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Put In: 178', Pulled Out: None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. 3839' to 170' Heavy mud - plug and 15 sacks cement. Plug and 10 sacks cement @ 40' to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Palmer Oil Corporation Address 415 Union National Bank Building, Wichita 2, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. A. H. Smith (employee of owner) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Smith

Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of July, 19 51

My commission expires 9/30/53. Notary Public. Olaf M. Kolling



WELL LOG - MILLER "A" #1

WELL OWNER: The Palmer Oil Corporation, etal

Location: SE SE NW

CONTRACTOR: The Palmer Oil Corporation

Section 18-98-20W

Rooks County, Kansas

Elevation: 2255 R.B.

Commenced: 6/19/51

Completed: 6/30/51

RESULTS: Dry Hole

Casing Record

8 5/8" - 178' cemented 125 sacks

Shale & shells	0	573	
Shale	573	1110	
Sand & shale	1110	1140	
Shale	1140	1145	
Shale & sand	1145	1770	
Anhydrite	1770	1799	
Shale & shells	1799	2265	
Shale & lime	2265	2623	
Lime & shale	2623	3540	
Lime	3540	3745	
Lime & shale	3745	3807	
Cherty Conglomerate	3807	3823	
Chert	3823	3839	Rotary TD

Formation Tops (R. B.)

Topeka	3277
Heebner	3488
Toronto	3512
Lansing	3527
Base K. C.	3742
Conglomerate	3796

DRILL STEM TEST - 3692 - 3745 Tool open 30 minutes. Very weak blow for 15 minutes - recovered 10 feet heavy mud with a few specks of tarry oil.

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

By A. H. Smith

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in said county and state this 24th day of July, 1951.

Olaf M. Kolling
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

My commission expires: 9/30/

PLUGGING
FILE SEC 18 T 9 R 20W 25 1951
BOOK PAGE 92 LINE 5
REGISTRATION DIVISION
Wichita, Kansas