


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County, Sec. 29 Twp. 9 Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW SE NE  
Lease Owner Southern States Oil Company  
Lease Name Lambert Well No. 3  
Office Address Box 1365, Great Bend, Kansas 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plat

Date Well completed February 7 19 77  
Application for plugging filed February 7 19 77  
Application for plugging approved February 7 19 77  
Plugging commenced February 7 19 77  
Plugging completed February 7 19 77  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 3914  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud pumped 70 sacks 50/50 Pozmix, 6% Gel thru drill pipe @ 1800'  
Mud to 240' w/20 sacks cement thru drill pipe.  
Mud to 40' w/ $\frac{1}{2}$  sack hulls plug and 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 11 1977

2-11-77

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Larry Curtis (employee of owner) or ~~(owner or operator)~~  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis  
P. O. Box 823, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 77

My commission expires April 11, 1978

Dorothy M. Hague  
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: January 31, 1977  
 DATE COMPLETED: February 7, 1977

Southern States Oil Company  
 LAMBERT # 3  
 NW SE NE  
 Sec 29-T9-R20W  
 Rocks County, Kansas

ELEVATION: 2301 K.B.

0 - 70'	Shale, Post Rock
70 - 95'	Sand
95 - 625'	Gray Shale
625 - 1290'	Shale and Sand
1290 - 1525'	Dakota Sand
1525 - 1797'	Shale
1797 - 1830'	Anhydrite
1830 - 2310'	Shale and Lime
2310 - 3554'	Lime and Shale
3554 - 3558'	Shale
3558 - 3575'	Lime and Shale
3575 - 3811'	Lime
3811 - 3899'	Lime and Shale
3899 - 3914'	Dolomite
3914'	RTD

FORMATION TOPS

Dakota Sand	1290
Anhydrite	1797
Hebner	3554
Toronto	3575
Lansing K.C.	3592
Base K.C.	3811
Arbuckle	3899
RTD	3914

SURFACE PIPE:  
 Set used 8 5/8", 28# pipe  
 at 255' w/150 sacks Common,  
 2% Gal, 3% cc.

STATE OF KANSAS COMMISSION  
 FEB 11 1977  
 2-11-77  
 COUNTY OF BARTON  
 RECORDS

AFFIDAVIT

STATE OF KANSAS }  
 COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 9th day of February, 1977.

Alvin M. Hogue  
 Notary Public

My Commission Expires: April 11, 1978