


15-163-20649-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Rooks County. Sec. 29 Twp. 9 Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE NW NE  
Lease Owner Southern States Oil Co.  
Lease Name Lambert Well No. 2  
Office Address Box 1365 Great Bend, Ks. 67530  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Date Well completed December 22, 1976  
Application for plugging filed December 22 1976  
Application for plugging approved December 22 1976  
Plugging commenced Dec. 22 1976  
Plugging completed Dec. 22 1976  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3915  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

None full of heavy mud.  
Bottom plug at 800' with 70 sacks cement (-50/50 pozmix, 6% Gel) thru drill pipe  
Middle plug at 240' with 20 sacks " " " thru drill pipe  
Top plug at 40' w/ 7/8 sack hulls, plug and 10 sacks cement.

DEC 27 1976  
12-27-76

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF Kansas COUNTY OF Barton, ss.  
Larry Curtis (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis  
Box 823 - Great Bend, Ks. 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of December, 19 76

My commission expires April 11, 1978

Barth M. Hague  
Notary Public.

Drillers' Well Log

Date Commenced: December 16, 1976  
 Date Completed: December 22, 1976

Southern States Oil Co.  
 Lambert #2  
 SE NW NE  
 Sec. 29, Twp. 9, Rge. 20 W  
 Rooks County, Kansas

Elevation 2003 KB

- 0 - 72' Surface soil & post rock
- 72 - 263' Sand
- 263 - 890' Shale
- 890 - 940' Red Bed
- 940 - 1283' Shale & Sand streaks
- 1283 - 1479' Dakota Sand
- 1479 - 1528' Shale & Dakota Sand
- 1528 - 1772' Shale
- 1772 - 1866' Anhydrite
- 1866 - 3555' Shale & Lime
- 3555 - 3558' Shale
- 3558 - 3575' Lime & Shale
- 3575 - 3593' Lime & Shale
- 3593 - 3813' Lime
- 3813 - 3915' Lime - Shale
- 3915' RD

Formation Data

Dakota Sand	1283'
Anhydrite	1772
Heabner	3555
Tonawanda	3575
Kansas City	3593
Base K.C.	3813
Conglomerate	3877
RD	3915

RECEIVED  
 DEC 27 1976  
 COUNTY CLERK  
 ROOKS COUNTY, KANSAS

Surface Pipe: Set used 28", 8-5/8" pipe at 263' with 160 sacks cement, 2% gel, 3% cc.

Affidavit

State of Kansas  
 County of Barton ss.

Larry Curtis of lawful age does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 24 day of December 1976

My Comm. Expires:  
April 11, 1978

Veracity M. Hagne  
 Notary Public