

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks

County. Sec. 29 Twp. 9S Rge. 20 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SE

Lease Owner Nadel and Gussman

Lease Name Christine Kern Well No. 2

Office Address P. O. Box 309, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 5-19-52

Application for plugging filed 5-19-52

Application for plugging approved 5-19-52

Plugging commenced 5-19-52

Plugging completed 5-19-52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3897 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	145'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from T.D. to 135' - set plug and cemented with 15 sacks cement. Set top plug at 40' and cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

5-27-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Reserve Drilling Company

Address 703 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. C. Hay (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Hay


703 Union National Bank Bldg.

(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of May 1952

My commission expires Nov. 3, 1952

Notary Public.



WELL LOG

NADEL AND GUSMAN

CHRISTINE No. 2

NW NW SE
29-9-20W
Rooks County, Kansas

Comm: 5-9-52
Comp: 5-18-52

Casing: 8-5/8" 145' v/100 Sax

Formations	Depth	Geological Top
Sand and shale	148	
Shale and shells	445	
Shale, sand and shells	1260	Heebner 3522
Sand, shale, shells, red bed	1773	Toronto 3543
Anhydrite	1805	Lansing-Kansas C. 3562
Shale and broken lime	2415	Base Kansas City 3769
Lime and shale	3842	Conglomerate 3842-3897
Conglomerate	3897	

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. C. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Christine No. 2 Well in the NW NW SE 29-9-20W, Rooks County, Kansas.

PLUGGING

FILE SEC 29-9-20W
BOOK PAGE 19-3

Subscribed and sworn to before me on this 23rd day of May, 1952.

STATE CORPORATION COMMISSION

L. C. Hay

Walter Babb

Notary Public

My commission expires Nov. 3, 1952