

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County, Sec. 28 Twp. 9 Rge. 20 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NW SE SW

Lease Owner Nadel & Gussman

Lease Name Kern Well No. 4

Office Address P. O. Box 158 Plainville, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 11-4-66 19

Application for plugging approved 11-5-66 19

Plugging commenced 11-15-66 19


Plugging completed 12-6-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey



Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3863 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	159	None
				5 1/2	None	1213

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cleaned out cellar. Broke off tubing head.

Moved in. Rigged up. Mixed and dumped 5 sacks of cement on bridge at 3800'.

Worked pipe. Shot pipe at 3011' - 2030' and 1525'. Working pipe.

Working pipe. Shot pipe at 1306' and 1210'. Working pipe. Pulling pipe.

Finished pulling pipe.

Plugged well with 18 sacks of gel and 70 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1966
12-19-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16 day of December, 1966

My commission expires May 27, 1969

Notary Public.

15-163-01766-00-00

WELL LOG

NADEL AND GUSSMAN

KERN No. 4

NW SE SW 28-9-20W
Rooks County, Kansas

Comm. 3-26-51
Comp. 4-4-51

Casing: 8-5/8" 159' w/110 Sax
5-1/2" 3861 1/2' w/125 Sax

Formation	Depth
Surface, sand and shale	159
Shale and shells	350
Shale, shells and sand	1045
Shale and shells	1250
Sand	1485
Shale and red bed	1675
Shale and shells	1779
Anhydrite	1821
Shale and shells	2280
Broken lime	2507
Lime and shale	3562
Lime	3810
Conglomerate	3848
Simpson Shale	3861
Arbuckle Lime	3863

Geological Tops

Heebner	3527
Toronto	3548
Lansing-Kansas City	3566
Conglomerate	3839
Simpson Dolomite	3848
Simpson Shale	3850
Arbuckle	3861
R.T.D.	3863

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1960

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

L. C. Hay, of lawful age being duly sworn deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of the Kern No. 4 Well in the NW SE SW 28-9-20W, Rooks County, Kansas.

R. C. Hay

Subscribed and sworn to before me this 9th day of April, 1951.

W. C. Babbs
Notary Public

My commission expires Nov. 3, 1952.