

State of Kansas



JOHN CARLIN
MICHAEL LENNEN
R. C. (PETE) LOUX
PHILLIP R. DICK
JUDITH MCCONNELL
BRIAN J. MOLINE

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE SECRETARY
GENERAL COUNSEL

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

December 8, 1983

EXPIRES

MAR 8 1984

THIS NOTICE

WELL PLUGGING NOTICE

THIS NOTICE

MAR 8 1984

EXPIRES

Energy Three, Inc.
P.O. Box 1505
Great Bend, Kansas, 67530

Lambert Lease well #1
NE SW NE Sec. 29-9S-20W
Rooks County
3955'

Plugging Contractor Not Available At This Time

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Yours very truly,

Carol J. Larson, Administrator

Please submit your proposal for plugging the above captioned well to

District #6 1014 Cody, Hays, KS., 67601, 913-628-1200

seven days prior to plugging the well (KAR-82-3-113)

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 163 - 20,642 (of this well)
Lease Owner ENERGY THREE, INC. OPERATOR # 5430
Address P. O. Box 1505 GREAT BEND, KANSAS 67530
Lease (Farm Name) LAMBERT Well No. 1
Well Location NE SW NE Sec. 29 Twp. 9S Rge. ~~9E~~ 20 (W)
County ROOKS Total Depth 3955 Field Name _____
Oil Well Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A _____
Well Log attached with this application as required YES
Date and hour plugging is desired to begin 8:00 A.M. 11-28-83

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
R. D. STANDLEE Address P.O. Box 1505 GREAT BEND, KANSAS 67530

Plugging Contractor NOT KNOWN AT THIS TIME License No. _____

Address _____

Invoice covering assessment for plugging this well should be sent to:

Name ENERGY THREE, INC.

Address P.O. Box 1505 , GREAT BEND, KANSAS

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____

Applicant or Acting Agent

Date: _____

NOVEMBER 22, 1983

DATE COMMENCED: October 11, 1976
DATE COMPLETED: October 19, 1976

Southern States Oil Company
LAMBERT # 1
NE SW NE
Sec 29-T9-R20W
Rooks County, Kansas

ELEVATION: 2295 K.B.

0 - 1118' Clay and Shale
1118 - 1130' Hard Sand
1130 - 1785' Shale and Sand Streaks
1785 - 1822' Anhydrite
1822 - 1921' Shale
1921 - 3544' Shale and Lime
3544 - 3548' Shale
3548 - 3566' Lime and Shale
3566 - 3799' Lime
3799 - 3882' Lime and Shale
3882 - 3955' Dolomite
3955' RTD

FORMATION TOPS

Anhydrite 1785
Heebner 3544
Toronto 3566
Lansing 3583
Base K.C. 3799
Arbuckle 3882
RTD 3955

SURFACE PIPE:

Set used 8 5/8", 28# pipe
at 261' w/160 sacks Common,
2% Gel, 3% cc.

PRODUCTION PIPE

Ran new 5 1/2", 15 1/2# casing at
3954' w/150 sacks Common, 10%
salt, 10 bbl water ahead,
.75% CFR2.

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

Larry Curtis, of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 21st day of October, 1976.

RECEIVED
STATE CORPORATION COMMISSION

Harold M. Hague

Notary Public

My Commission Expires: April 11, 1978

NOV 23 1983