

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 125-25
LOCATION C NW NW SW
SEC. 13 TWP. 9 RGE. 19

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 4 Lease Boisvert
Operator Eli Boisvert c/o W. E. Wickizer Mgr Wakeeney, Kans
Address _____
Field _____ County Rooks
Total Depth 3571 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 170' circulated with cement - 5 1/2" at 3570' with
100 sax cement behind, Perforated at 3305', squeezed off
perforations with cement .

Sand to 3560', set 4 sax cement with dump bailer, pulled
2825' 5 1/2", filled with mud to 170', set rock and 10 sax
cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

PLUGGED
FILE SEC 13 9 1947
BOOK PAGE 123 23

10-9-53

[Signature]
District Conservation Agent
Date 10-7-53