

140
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1962
11-8-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morris Sitrin
Complete Address: Box 286 El Dorado, Kansas
Lease Name Boisvert Well No. 2
Location NW SW SW Sec. 13 Twp. 9 Rge. (E) (W) 19
County Rooks Total Depth 3536
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling Co
Address: Great Bend, Kansas License No. 49
Operation Completed: Hour 1PM Day 7 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 140', circulated with cement - 5 1/2" 3533' with 100 sax cement behind & squeezed in Dakota section - amt cement ?

Filled with sand to 3520', set 4 sax cement with dump bailer - pulled 720' 5 1/2" to 550', circulated hole with heavy gel mud through 5 1/2" at 550', displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', cement 35' to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/8/62
INV. NO. 5989-W

Signed: *E. J. Perry*
Well Plugging Supervisor