

15-163-03045-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1968
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name K & G Oil CompanyComplete Address: Box 403 Plainville, KansasLease Name Hilgers Well No. 2Location NE NW NE Sec. 13 Twp. 9 Rge. 19 (E) X (W) XCounty Rooks Total Depth 3500'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Co. Tools By HOWCOAddress: License No. Operation Completed: Hour 1:30 P Day 26 Month 7 Year 1968

The Above well was plugged as follows:

Total depth 3500' 10 3/4 csg set at 270' cwc.5 1/2 csg set at 3500' cw 150 sc cement.5 1/2 csg perf. 6 sets from (3174-3500)5 1/2 csg perf. and squeezed at 1093' W/200 sc cement.No pipe recov.Pumped thru 5 1/2 plg container with 35 sc gel W/10 sc hulls, plug and 70 sc 50-50 poz
cement W/6% gel. Max. pres. 1600 lbs. SI pres. 500 lbs.Pumped down annulus (103/4-5 1/2) with 30 sc 50-50 poz cem. W/6% gel. Pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/29/68INV. NO. 8204-USigned: R. L. Murrey
Well Plugging Supervisor