

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CR-3
REVISED
RECEIVED
STATE CORPORATION COMMISSION
MAY 08 1978
5-8-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163- 20341-00-00 (of this well)

Operator's Full Name Hinkle Oil Co.

Complete Address 1016 Union Center, Wichita, Kansas 67202

Lease Name Kern "C" Well No. 2

Location NE NE NE Sec. 15 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth ³⁶³²
3681'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 9:40 A Day 5 Month 5 Year 1978

The above well was plugged as follows:

Total Depth ³⁶³² 3681' 8 5/8 csg set 290' cwc 250 sk.

4 1/2 csg set 3632' cw 225 sk cem.

4 1/2 csg PBD 3390' with perf. (3352'-3355')

Filled 4 1/2 csg W/sd (3390'-3300') dumped 3 sk cem W/dump bailer. (3300'-3270')

Cutoff & recovered 593' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water W/200 lbs

hulls, released plug & 140 sk 50-50 poz 6% gel & shutin. FPP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

DATE 5-8-78

Signed: Geo. Massey
Well Plugging Supervisor

INV. NO. 7268-W