

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-17-72
MAR 17 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Company & Woodman -Iannitti Drilling
Complete Address 800 Bitting Bldg., Wichita, Kansas
Lease Name Gish Well No. 1
Location SW SW SE Sec. 15 Twp. 9 Rge. (E) (W) 20
County Rooks Total Depth 3786'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 8:30 A Day 15 Month 3 Year 1972

The above well was plugged as follows:

RTD 3786' 8 5/8 csg set at 176' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/17/72
INV. NO. 5370-u