

15-163-20552-00-00



KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
12/30/74
DEC 30 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Inc.

Complete Address 370 W. Wichita Ave. Russell, Kansas

Lease Name Smith "B" Well No. 1

Location C NW NE Sec. 11 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3630'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 2:45 P Day 29 Month 12 Year 1974

The above well was plugged as follows:
RTD 3630' 8 5/8 csg set at 209' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.
Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. J. Massey
Well Plugging Supervisor

INVOICED

DATE 1/3/75
INV. NO. 561-W