

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CSW NE SE

SEC. 18 TWP. 9 RGE. 20

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease _____ Towns _____

Operator Skelly Oil Co Address Hutchinson, Kans

Field _____ County Rooks

Total Depth 3910 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 290' circulated with 150 sax cement.

~~Sax~~ Circulated hole with heavy mud, spotted 25 sax cement on bottom through drill pipe, mud to ~~290~~ 270', set cementing plug and displaced 25 sax cement at 270' through drill pipe, mud to 70', set cementing plug and filled with cement from 70' to 0'.

Cementing by Halliburton Co.

3-20-52

J. P. Perry

District Conservation Agent

Date 3-18-52

PLUGGING
FILE SEC 18 T 9 R 20
BOOK PAGE 2 LINE 34