



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 30 1974
12-30-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name R. P. Nixon Operations

Complete Address Box 589 Russell, Kansas 67665

Lease Name Paul Miller Well No. 3

Location SW NE NW Sec. 18 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3828'

Abandoned Oil Well Gas Well Input Well XXX SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Charlie Crowe Casing Pulling

Address Box 706 Hays, Kansas 67601 License No. 733

Operation Completed: Hour 2 P Day 26 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3828' 8 5/8 csg set at 279' cwc

5 1/2 csg set at 3827' cw 100 sk cmt.

5 1/2 csg PBD 3815' & perf. (3805-3812)

Filled 5 1/2 csg W/sd (3815-3775) dumped 4 sk cmt W/dump bailer. (3775-3745)

Cutoff & recovered 1250' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg 20 sk gel & water W/300 lbs hulls, 70 sk 50-50 poz 6% -

10 sk gel & water -released 8 5/8 plug & pumped 50 sx 50-50 poz 6% by Sun Cem. Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo G. Massey
Well Plugging Supervisor

INVOICED

DATE 12/31/74

INV. NO. 547-W