

4
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: 1860 Lincoln St. Denver, Colorado 80203

Lease Name Paul Miller Well No. 2

Location NE NE NW Sec. 18 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3795

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Co. tools by HOWCO

Address: License No.

Operation Completed: Hour 2 P Day 6 Month 2 Year 1968

The Above well was plugged as follows:

Total Depth 3795 8 5/8 csg set at 276' cwc 175 sc.

5 1/2 csg set at 3784' cw 175 sc cement.

Tubing stuck at 1420'. Pulled into and recov. same.

Hole in 5 1/2 csg at Approx. 1200'. Pumped plg to top of fish.

Pumped down 5 1/2 csg W/350 Cu. Ft. cement and shutin W/500# pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/8/68
INV. NO. 7332-W

Signed: Leo J. Massey
Well Plugging Supervisor