

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.  
Address: 250 N. Water, Suite 300  
Phone: (316) 267-3241 Operator License #: 30606  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 2/8/07 (Date)  
by: Barry Metz (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Kansas City Depth to Top: 3750 Bottom: 3755 T.D. \_\_\_\_\_  
Lansing Kansas City Depth to Top: 3767 Bottom: 3771 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 065-03228-0000  
Lease Name: Diebolt B  
Well Number: 9  
Spot Location (QQQQ): NW - NE - NE -  
330 Feet from  North /  South Section Line  
4290 Feet from  East /  West Section Line  
Sec. 33 Twp. 10 S. R. 23  East  West  
County: Graham  
Date Well Completed: 3/56  
Plugging Commenced: 3/14/07  
Plugging Completed: 3/14/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	218	8 5/8	218	0
	Production	Surface	3778	5 1/2	3778	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


RIH Tbg to 1500'. RU Allied Cementing. Circulate hole clean with 40 BSW. Mixed 110 sx 60/40 Poz, 10% gel w/ 200# hulls to circ cement to surface. TOH w/ 2 3/8" tbg. Tied onto 5 1/2" csg. Pumped 165 sx & 600# hulls, 500# max pressure. Let set 30 min. Topped off 5 1/2" csg w/25 sx. Tied onto 8 5/8". Pumped 40 sx 200# max pressure, 100# ISIP. Plugged at 1:00 pm. Witnessed by Rich Williams, KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606  
Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.  
State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears  
(Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 2nd day of May, 20 07  
Susan Brady My Commission Expires: 11-4-07  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MAY 04 2007

CONSERVATION DIVISION  
WICHITA, KS