

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc. Address: 250 N. Water, Suite 300 Phone: (316) 267-3241 Operator License #: 30606 Type of Well: Injection Docket #: E-16,643 The plugging proposal was approved on: 3/27/07 by: Darrel Dipman Is ACO-1 filed? [X] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - Docket #E-16,643-0004 Lease Name: Texaco Cahoj Unit Well Number: 6 Spot Location (QQQQ): C - SE - SW - 660 Feet from [ ] North / [X] South Section Line 3300 Feet from [X] East / [ ] West Section Line Sec. 3 Twp. 01 S. R. 34 [ ] East [X] West County: Rawlins Date Well Completed: 8/70 original completion date Plugging Commenced: 3/27/07 Plugging Completed: 3/27/07

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include Surface and Production formations.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set. TIH w/80 jts @ 2500'. RU Swift Services. Pumped 74 bbl cmt, 135 sx SMD cmt w/400# cotton seed hulls. Established circulation w/14 bbl. TOH w/40 jts, bottom tbg @ 1250'. Hooked up cement truck. Pumped 14 bbl, 30 sx SMD cmt w/100# cotton seed hulls, had good cement in returns. TOH w/last 40 jts 2 3/8" tbg. Top off csg w/15 sx SMD. Hook up to 8 5/8", pumped 30 sx SMD, press up to 400#, SI & held. Plug job witnessed by Darrel Dipman, KCC

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606 Address: 250 N. Water, Suite 300; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc. State of Kansas County, Sedgwick, ss.

Susan Sears, Operations Engineer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Susan Sears (Address) 250 N. Water, Suite 300; Wichita, KS 67202



SUBSCRIBED and SWORN TO before me, this 2nd day of May, 2007. Susan Brady, Notary Public. My Commission Expires: 11-4-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED KANSAS CORPORATION COMMISSION

MAY 04 2007

CONSERVATION DIVISION WICHITA, KS