

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. B2-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Timberline Oil & Gas Corporation
Address: 4000 Penrose Place, Rapid City, S.D. 57702
Phone: (605) 341-3400 Operator License #: 9232
Type of Well: EOV Docket #: E-13600
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)
The plugging proposal was approved on: per CP213 (Date)
by: Steve Pfliefer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-151-30101
Lease Name: Miskimen
Well Number: W-1
Spot Location (OOQQ): 70°W NE NW SW
50 Feet from North / South Section Line
3960 Feet from East / West Section Line
Sec. 32 Twp. 26 S. R. 12W East West
County: Pratt
Date Well Completed: _____
Plugging Commenced: 3-28-07
Plugging Completed: 4-2-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	684'	None
				4-1/2"	4305'	2011'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4140' and 4 sacks cement, Cut casing loose @2011', pulled up to 723', pumped 10 sxs. gel & 50 sxs. cement, pulled up to 300', pumped 30 sxs. cement and circulated 40 sxs. cement from 40' to surface. 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Timberline Oil & Gas Corporation
State of Kansas County: Rice ss.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 19 2007

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 16th day of April, 2007

Irene Herzberg
Notary Public

My Commission Expires

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

TYPE OR PRINT

NOTICE OF INTENTION TO DRILL

C-1

15-151-20, 020

TO BE FILED WITH THE STATE CORPORATION COMMISSION PRIOR TO COMMENCEMENT OF WELL

1. Operator Tidewater Oil Company Address Box 752, Drumright, Oklahoma
2. Lease name V. E. Miskimen Well No. W-1 County Pratt
3. Well Location 1320' EWL & 50' NSL Sec. 32 Township 26S Range 12W
4. Well to be drilled 50 ft. from nearest lease line.
5. Drilling Contractor Red Tiger Drilling Co. Address 1720 Wichita Plaza, Wichita, Kansas
6. Type of equipment: Rotary Cable Tool Approx. date operation to begin April 29, 1967.
7. Well to be drilled for Oil Gas Disposal Input Estimated Total Depth of Well 4375 ft.
8. Depth of deepest fresh water well within one mile of location Unknown ft. If none exists, write NONE Unknown.
9. Ground elevation at location is approx. Unknown ft. higher or Unknown ft. lower than ground elevation at water well.
10. Depth of the deepest municipal water well within three miles of location _____ ft. If none exists, write NONE None.
11. Operator states that he will set surface pipe at least 25 ft. below all Tertiary or unconsolidated deposits and, taking into consideration differences in ground elevations, that the minimum depth necessary, to the best of his knowledge and belief, to protect all fresh water zones is _____ ft. and operator agrees to set surface pipe at this location to a depth of not less than 675 ft. Alternate 1 Alternate 2 .

REMARKS:

(2)

P. Shackelford
E. Berg
e

Signature of Operator

W. H. McPhail

W. H. McPhail, Area Supt.

Place
5¢
Stamp
Here

**State Corporation Commission of Kansas
Conservation Division
500 Insurance Building
212 North Market
Wichita, Kansas 67202**

RECEIVED
STATE CORPORATION COMMISSION

MAY 4 1967

CONSERVATION DIVISION
Wichita, Kansas

(IF PREFERRED, MAIL IN ENVELOPE)