

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21849-00-00
Spot: W2SESE Sec/Twnshp/Rge: 3-30S-7W
735 feet from S Section Line, 915 feet from E Section Line
Lease Name: KYLE Well #: 4-3
County: KINGMAN Total Vertical Depth: 4250 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4246		125 SX
SURF	8.625	232		200 SX

\$ 138.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2007 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 532-9235

Proposed Plugging Method: SAND BACK 50 FT ABOVE PERFS. WITH 5 SKS CAP, REC. PIPE. 35 SKS @1200, 35 SKS @ 700', CIRC. CMT FROM 280 TO 0.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/23/2007 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE COVERED WITH SAND FROM 4208' (PBSD) TO 4100' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 3060' AND PULLED TO 1200' WHERE 35 SKS OF CMT. WAS SPOTTED. CASING WAS PULLED TO 700' AND 35 SKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 280' WHERE CMT WAS CIR. TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4172	4176		
4158	4168		

INVOICED
DATE 4-27-07
INV. NO. 2007061661

Remarks: CONSOILDATED CEMENT CO. TICKET # 17089 60/40 POZMIX 4% GEL 85 SKS @ 280 FT.

Plugged through: CSG

District: 02

Signed _____
(TECHNICIAN)

M

RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2007

CONSERVATION DIVISION

Form CP-2/3

DR