

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21329-00-00  
Spot: E2SWNE Sec/Twnshp/Rge: 11-33S-6W  
3300 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: CAROTHERS BROS Well #: 2  
County: HARPER Total Vertical Depth: 4550 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PARKWAY  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comment                |
|--------|-------|------------|-------------|------------------------|
| PROD   | 5.5   | 4549       | 3630        | 100 SX <sup>PST</sup>  |
| SURF   | 8.625 | 272        |             | 185 SX <b>\$147.88</b> |

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYR Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: AS KCC REQUIRES.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 02/27/2007 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE COVERED WITH SAND TO 4330' AND CAPPED WITH 5 SKS OF CEMENT. CASING WAS RECOVERED FROM 3630' AND PULLED TO 1100' WHERE 35 SKS OF CMT WAS SPOTTED, CASING WAS PULLED TO 600' WHERE 35 SKS OF CMT WAS SPOTTED. CASING WAS PULLED TO 325' WHERE CMT WAS CIR. TO SURFACE.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4481 | 4484 |      |          |
| 4398 | 4407 |      |          |
| 4382 | 4388 |      |          |

**INVOICED**  
DATE 4-27-07  
INV. NO. 20070616602

Remarks: UNITED CMTG TICKET # 6126 60/40 POZMIX 4 % GEL

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS

*m*

*PST*