

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21542-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 31-32S-9W  
2215 feet from S Section Line, 5080 feet from E Section Line  
Lease Name: HENDRICKS UNIT Well #: 2-31  
County: HARPER Total Vertical Depth: 3765 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PARKWAY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3764	3020	125 SX CMT. <i>Plus</i>
SURF	8.625	307		225 SX CMT. <i>\$1122-36</i>

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2007 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 727-3410

Proposed Plugging Method: AS KCC REQUIRES.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/05/2007 4:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS WERE COVERED WITH SAND TO A DEPTH OF 3610' AND CAPPED WITH 4 SKS OF CMT.. CASING WAS RECOVERED FROM 3020' AND PULLED TO 1400' WHERE 35 SKS OF CMT. WAS SPOTTED. CASING WAS PULLED TO 850' WHERE 35 SKS OF CMT WAS SPOTTED. CASING WAS PULLED TO 360' WHERE CMT. WAS CIRC. TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3666	3681		

**INVOICED**  
DATE 4-27-07  
INV. NO. 2007061602

Remarks: ALLIED CMTG TICKET# 60/40 POZMIX 4% GEL

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)  
**RECEIVED**  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS

*m*

*PRT*